BRUHAT BANGALORE MAHANAGARA PALIKE

Office Of The Executive Engineer, Dasarahalli Division

SCHEDULE-B

Name of work:Roads and Foothpath Maintainance in Ward No.13 Shettyhalli Sub division

Sl No	Description of Work	Unit	Quantity as per Estimate	Quoted Rate	
				In Figures	In Words
1	KSRRB 300-3. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. (Page No. 143/ Item No. 19.1/ PWD SR 2018-19)	Cum	333.60	137.80	Rupees One Hundred Thirty Seven And Paise Eighty Only
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18 pwd 2018-19)	Cum	166.80	5509.33	Rupees Five Thousand Five Hundred Nine And Paise Thirty Three Only
3	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum) (Page No. 175.tem No.22.6.1,PW,P & IWTD SR 2018-19)	Cum	166.80	5354.02	Rupees Five Thousand Three Hundred Fifty Four And Paise Two Only
4	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.(Page No. 178.tem No.22.7,PW,P & IWTD SR 2018-19)	Sqm	1112.00	72.08	Rupees Seventy Two And Paise Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP, Bengaluru

Scanned with CamScanner